

**IMIMPROVEMENTS TO ROADS AND DRAINS AT MAHALAKSHMI NAGAR IN WARD NO. 14, BAGALAGUNTE, DASARAHALLI-SUB-DIVISION,
SL. NO. 06, G.O. NO. 88, (PACKAGE NO. - DHZ 01)**

Sl. No.	Description of Work	Chainage		Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
		from	to								
1	KSRRB M200-13.1. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. II. By Mechanical Means. A. Cement Concrete Grade M-15 & M-20. MORTH Specification No. 202 (PW,P& IWTD SR 2018-19, Pg No 139 Item No.18.20)										
	Dismantling of Drain										
	4th main road (LHS)	0.00	209.00	Cum	1	209.00	1.80	0.10	37.62		
	5th main road	0.00	236.00	Cum	2	236.00	1.80	0.10	84.96		
	6th main road (LHS)	0.00	190.00	Cum	1	190.00	1.80	0.10	34.20		
	Total								156.78	413.40	64,812.85
2	Removing B.S. slab of Drain and stacking (PW,P& IWTD SR 2018-19, Pg No 27 Item No.5.32)										
	6th main road (RHS)	0.00	150.00	Sqm	1	150.00	1.35		202.50		

Sl. No.	Description of Work	Chainage		Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
		from	to								
6	KSRRB M2200-5.12. Providing and laying Design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.7 cum and fine aggregates @ 0.47 cum, with superplasticiser @ 3lts conforming to IS9103-1999 Reaffirmed-2008. i) Upto 5 m height. (PW,P& IWTDR SR 2018-19 P-227, I-28.7.12)										
	M25 Concrete - For drain Raft										
	4th main road (LHS)	0.00	209.00	Cum	1	209.00	0.90	0.15	28.22		
	5th main road	0.00	236.00	Cum	2	236.00	0.90	0.15	63.72		
	6th main road	0.00	190.00	Cum	2	190.00	0.90	0.15	51.30		
	M25 Concrete - For drain Wall										
	4th main road (LHS)	0.00	209.00	Cum	2	209.00	0.60	0.15	37.62		
	5th main road	0.00	236.00	Cum	4	236.00	0.60	0.15	84.96		
	6th main road	0.00	190.00	Cum	4	190.00	0.60	0.15	68.40		
	Total								334.22	5775.37	19,30,216.61
7	KSRRB M2200-6. Providing T.M.T. steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification. MORTH Specification No.1600 & 2200 -do- TMT Bars Fe 500(PW,P& IWTDR SR 2018-19, Pg No 229 Item No.28.8.2)										
					Drain concrete quantity			334.22			
	Quantity at 60 kg/ Cum of M25 concrete for Drains			Tonne					19.38		
									19.38	72,326.98	14,02,020.17
8	KSRRB M2200-1 Providing weep holes in Brick masonry / Plain / Reinforced concrete abutment, wing wall / return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including cost of materials, labour, HOM complete as per specifications. MORTH Specification No.2706 & 2200(PW,P& IWTDR SR 2018-19 P-229, I-28.10)										
	At 1.5m Center to Center Spacing										
	Drain										
	4th main road (LHS)	0.00	209.00	Rmt	139	0.15			20.90		
	5th main road	0.00	236.00	Rmt	315	0.15			47.20		
	6th main road	0.00	190.00	Rmt	127	0.15			19.00		
	Total								87.10	155.82	13,571.92
9	Removing and resetting of footpath slab (PW,P& IWTDR SR 2018-19 P-270, I-37.56)										
	For Drain Cover Slabs										
	4th main road (LHS)	0.00	209.00	Sqm	1	209.00	0.90		188.10		
	5th main road	0.00	236.00	Sqm	2	236.00	0.90		424.80		
	6th main road (LHS)	0.00	190.00	Sqm	1	190.00	0.90		171.00		
	Total								783.90		
	Considering 60% to removing and resetting								470.34		
	Resetting slabs within Ward using ward labours										
	6th main road (RHS)	0.00	150.00	Sqm	1	150.00	1.35		202.50		
	For Drain Cover BS Slabs										
	6th main road (RHS)	0.00	150.00	Sqm	1	150.00	0.90		135.00		

BRUHAT BENGALURU MAHANAGARA PALIKE

Sl. No.	Description of Work	Chainage from	to	Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
									807.84	208.82	1,68,693.15
10	Providing and fixing Precast RCC cover slabs of 100 mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortar including form work, lift charges, curing and concrete finished surface on both sides etc, and complete as per the directions of Engineer in charges. (Data Rate)										
	For Drain Cover Slabs										
	4th main road (LHS)	0.00	209.00	Sqm	1	209.00	0.90		188.10		
	5th main road	0.00	236.00	Sqm	2	236.00	0.90		424.80		
	6th main road (LHS)	0.00	190.00	Sqm	1	190.00	0.90		171.00		
	Total								783.90		
	Considering 40% to removing and resetting								313.56	1615.00	5,06,399.40
11	KSRRB 15.2.2 : Providing ruled pointing 20 mm deep to stone slab pavements with cement mortar 1:3, 20mm deep, after raking joints nicely lining, including cost of materials, labour, curing complete as per specifications. MORTH / Chapter 3 (PW,P & IWTD SR 2018-19, Item No. 15.8, Page No.115)										
	Pointing for resetting slabs			Sqm					807.84	49.06	39,631.05
12	KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials separately complete as per specifications. MORTH Specification No. 202 (PW,P & IWTD SR 2018-19, Item No. 18.47, Page No.140)										
	4th main road	0.00	209.00	Cum	1	209.00	4.30	0.10	89.87		
	Total								89.87	952.94	85,640.72
13	KSRRB 300-48. Scarifying kankar / gravel / metal crust by mechanical means upto 150mm thick, disposal of stuff including cost of all labour charges, HOM complete as per specifications. MORTH / Chapter 3 (PW,P & IWTD SR 2018-19, Item No. 19.54, Page No.146)										
	4th main road	0.00	209.00	Sqm	1	209.00	4.30		898.70		
	Total								898.70	25.44	22,862.93
14	KSRRB 300-58. Compaction of original ground by mechanical means including filling in depression occurring during rolling including cost of all labour, HOM complete as per specifications. MORTH I Chapter 3 (PW,P& IWTD SR 2018-19, Pg No 147 Item No.19.64)										
	4th main road	0.00	209.00	Sqm	1	209.00	4.30		898.70		
	Total								898.70	6.36	5,715.73
15	CONCRETE PAVEMENT KSRRB M600- Cement Concrete Pavements KSRRB M600-1. Providing and Constructing dry lean cement concrete mix CC 1:5:10 base with OPC 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @0.58cum over a prepared sub-base, coarse and fine aggregate conforming to IS: 383-2016, aggregate cement ratio not to exceed 15:1, Aggregate gradation after blending to be as per Table 600-1, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver, compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications. Clause 601 of MORTH V Revision and IS 456 Table-5 -do- with OPC at 150 kg/cum and coarse aggregate 0.86cum, fine aggregate 0.58cum using Concrete Batch mix Plant at 75 cum/hr capacity with fixed form paver. (PW,P& IWTD SR 2018-19 P-174, I-22.1.2)										
	4th main road	0.00	209.00	Cum	1	209.00	4.30	0.10	89.87		
	Total								89.87	3944.51	3,54,493.03
16	KSRRB M400-17. Providing, laying, spreading and compacting Crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No.406. (PW,P& IWTD SR 2018-19, Pg No 155, Item No. 20.18)										
	4th main road	0.00	209.00	Cum	1	209.00	4.30	0.10	89.87		
	Total								89.87	2001.28	1,79,855.03

BRUHAT BENGALURU MAHANAGARA PALIKE

Sl. No.	Description of Work	Chainage		Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
		from	to								
17	Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum, Coarse and fine aggregate conforming to IS 383-2016, with Superplastizer at 3 lts conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rammers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane of impermeable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine, and curing including cost of all materials, labour, hire charges of machineries, all lead & lift charges etc., complete as per specifications. -do- with OPC at 360 kg/cum and coarse aggregate 0.69cum, fine aggregate 0.46cum. (PW,P& IWTD SR 2018-19, Pg No 176 Item No. 22.6.1)										
	4th main road	0.00	209.00	Cum	1	209.00	4.30	0.16	89.87		
	Total							6.10	89.87	5354.02	4,81,165.94
18	KSRRB 500-2. Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials, labour, HOM complete as per specifications. Clause 501 of MORTH V revision (PW,P& IWTD SR 2018-19, Pg No 158, Item No. 21.2)										
	Cleaning Existing BT Surface										
	5th main road	0.00	236.00	Sqm	1	236.00	4.50		1062.00		
	6th main road	0.00	190.00	Sqm	1	193.00	5.10		984.30		
									2046.30	5.30	10,845.39
19	KSRRB 500-7. Providing and applying tack coat using 80/100 grade bitumen (VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. Clause 503 of MORTH V revision (PW,P& IWTD SR 2018-19 P-158, I-21.7).										
	For Existing BT Surface										
	5th main road	0.00	236.00	Sqm	1	236.00	4.50		1062.00		
	6th main road	0.00	190.00	Sqm	1	193.00	5.10		984.30		
									2046.30	12.72	26,028.94
20	Providing and laying bituminous concrete 40mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 507 of MORTH V revision as per IRC SP-53-2015. -do- using 40-60 TPH capacity HMP with mechanical paver grading II(30-45mm) with 5.4% of modified bituminous binder consisting of 4.97% of VG-30 bitumen (60/70 grade) and 0.43% of plastomeric thermoplastics (waste plastic) (PW,P & IWTD Bengaluru Circle SR 2018-19, Item No. 171 Page No.21.78.12)										
	Bituminous Concrete										
	5th main road	0.00	236.00	Cum	1	236.00	4.50	0.04	42.48		
	6th main road	0.00	190.00	Cum	1	193.00	5.10	0.04	39.37		
									81.85	8699.42	7,12,064.93
21	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete. (PW,P& IWTD SR 2018-19, Pg No 27 Item No.5.30)										
	New Kerb										
	4th main road	0.00	209.00	Nos	1	209.00			465.00		
	5th main road	0.00	236.00	Nos	2	236.00			1050.00		
	6th main road	0.00	190.00	Nos	2	190.00			846.00		
	Total								2361.00	435.84	10,29,010.00

Sl. No.	Description of Work	Chainage		Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
		from	to								
22	KSRRB M800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications, MORTH Chapter 8 (PW,P& IWTD SR 2018-19, Pg No 180, Item No. 24.1)										
	Kerb painting										
	4th main road	0.00	209.00	Sqm	1	209.00	0.35		73.15		
	5th main road	0.00	236.00	Sqm	2	236.00	0.35		165.2		
	6th main road	0.00	190.00	Sqm	2	190.00	0.35		133		
	Total								371.35	84.80	31,490.48
Removal of Unservicable soil, Loading, unloading and Cost of Haulage											
23	KSRRB M300-19 Removal of unserviceable soil including excavation, loading and disposal but excluding replacement by suitable soil which shall be paid separately as per clause 300.5 complete as per specifications MORTH Specification No. 301. (PW,P& IWTD SR 2018-19, Pg No 144, Item No.19.20)										
	Vide Item No 3, 4.			Cum					471.05		
									471.05	34.98	16,477.44
24	KSRRB M-100-1 Loading and Unloading of Stone Boulder / Stone aggregate / Sand Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH -100 / Chapter 1, (PW,P& IWTD SR 2018-19, Pg No 136, Item No.17.1)										
	Vide Item No 1 & 12.			Cum	1				246.65		
									246.65	57.00	14,059.05
25	KSRRB M100-4.1. Cost of haulage Excluding Loading and Unloading MORTH-100/Chapter 1 case-I surface road (PW,P& IWTD SR 2018-19, Pg No 136, Item No.17.4)										
	Vide Item No 23 & 24.			Cum					717.70		
	Rain Water Harvesting								717.70	69.12	49,607.65
26	Filling in foundation with granite/trap broken metal 100mm and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with lead up to 50m and lift 1.5m complete as per specifications.										
	For All Roads										
	a) 40mm Jelly.				7	0.31	0.40	0.87	1901.00		1659.46
					(3.142*0.63*0.63)/4						
	b) 20mm Jelly.			Cum	7	0.31	0.40	0.87	1901.00		1659.46
	c) Coarse sand.			Cum	7	0.31	0.30	0.65	2651.00		1735.63
	d) Fine Sand			Cum	7	0.31	0.20	0.44	2651.00		1157.08
	e) 12.5mm chips			Cum	7	0.31	0.30	0.65	1901.00		1244.60
27	Supplying, laying and jointing HDPE pipes of specified grade and conforming to IS 4984- 995 with latest amendments and conveying to work site including loading and unloading at both destinations and rolling and lowering into trenches, laying true to line and jointing of pipes and specials, giving hydraulic test as per relevant ISS with all lead and lifts including encasing the pipe around to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation, testing and commissioning. The rate is exclusive of required specials and fittings wherever necessary like saddle Tee, stub ends, flanged sets, bends, reducers etc. complete (Contractor will make his own arrangements for procuring water for testing) etc. for : HDPE Grade PE80-PN6.0, 630 mm dia. (Perforated Pipe for Rain Water Harvesting Pit) (BWSSB SR 2017-18, Pg No 121 Item No. 1.17 Code No. K010Q)										
	For All Roads										
	Rain Water Harvesting pit										
	0.63m dia HDPE Perforated Pipe. For 1.8 Mtr depth,			Rmt	12.60				12.60		
									12.60	10822.32	136361.25

BRUHAT BENGALURU MAHANAGARA PALIKE

[illegible]**CERTIFICATE:**

- | | |
|-----|---|
| i | This work comes within BBMP limits |
| ii | Certified that Personally Inspected the Work Spot. |
| iii | Certified that the estimate is prepared based on CSR of PWD Bangalore Circle 2018-19. |
| iv | Estimate is prepared Making Use of essential item of work as per site Conditions in safest way of Execution in most economical way. |
| v | This work is not included in any other program of work. |

For Alcon Consulting Engineers (India) Pvt. Ltd.

**Alcon Consulting Engineers (I) Pvt. Ltd.,
Bengaluru**

**Assistant Engineer,
Ward No-14
BBMP**

Assistant Executive Engineer,
Shettyhalli/Dasarahalli/PLA/Hegganahalli
Division
BBMP

Executive Engineer,
Dasarahalli Division
BBMP

ADMINISTRATIVELY SANCTIONED FOR Rs. 99.00

(Rupees Ninety Nine lakhs only.....)

Under the Head of Account P-3227 SC-SP/TSP

Nutrient triangle Nava Bengaluru Yasane
Nam staple thana Yasane

Registered as no EED.D./AS. 173/19-21 Subject
to conditions contained in Enclosed Memo

No. EE/DDL/25 / 123/19-20 Dt: 16/11/2019

JE/AE.

(DASARAHALLI) BBMP